

**Table 1. Summary of Project Refinements (based on 100% construction drawings)**

<b>Project Element</b>	<b>Levee Deficiency</b>	<b>Previous Location</b>	<b>Revised Location</b>
Bear River Levee Reconstruction	Through-seepage, freeboard	Bear River Station 121+00 to 140+00	Bear River Station 122+00 to 130+00
Bear River Water-side Impervious Zone	Through-seepage	not included previously	Bear River Station 130+00 to 139+00
Bear River Levee Raise	Freeboard	Bear River Station 158+50 to 169+00	Bear River Station 139+00 to 144+00 and 147+70 to 168+80
Bear River Erosion Protection	Slope erosion and scour	Bear River Station 150+00 to 170+00	Bear River Station 164+00 to 168+80 and 168+50 to 169+15
Pump Station No. 6 Relocation	Under-seepage	Bear River Station 140+00	Bear River Station 141+00
WPIC Borrow Ditch Fill	Under-seepage	WPIC Station 0+00 to 45+00, 95+00 to 106+50, and 115+00 to 120+00	WPIC Station 0+00 to 130+00
WPIC Water-side Levee Raise	Freeboard	not included previously	WPIC Station 0+30 to 137+50
WPIC Water-side Levee Raise	Freeboard	not included previously	WPIC Station 205+50 to 275+70
WPIC Water-side Levee Raise	Freeboard	not included previously	WPIC Station 284+10 to 305+00
WPIC Land-side Levee Raise	Freeboard	WPIC Station 296+00 to 332+50	WPIC Station 305+00 to 311+58
WPIC Slurry Wall	Under-seepage	WPIC Station 252+50 to 261+50	WPIC Station 254+65 to 260+00 and 276+56 to 287+00